

Digital Alarm Unit (DAU)

Product Description

The digital alarm unit has been specifically designed to provide remote visual and audible alarm warning for HVAC systems / plant.

Five seconds (variable up to 8.5 minutes) after receiving a 24v ac/dc signal the unit will go into alarm, with both sounder and flashing LEDs operating. Pushing the left pushbutton will silence the sounder for 4 – 10 , after which it will sound again. The LEDs will continue to flash as long as the signal remains.

Pushing and holding in the right hand push button tests the unit.



Features:

- Aesthetically pleasing enclosure
- 24V ac/dc operation
- Pre-wireable base, Unit plugs onto base after decoration.
- Mute facility
- Manual test facility
- Wall or control panel mountable

Terminal Number	1	2	3	4	5	6	7	8	9	10	11	12
	Spare				VFC	VFC	Spare				0V	24v ac/dc
					Alarm input via relay/ integrator							

